



March 28, 2024

ADDENDUM NO. 1
ROOF REPLACEMENT AT GLENVIEW TRANSFER STATION
SOLID WASTE AGENCY OF NORTHERN COOK COUNTY (SWANCC)
PROJECT NO. 23122

Solid Waste Agency of Northern Cook County (SWANCC)
77 West Hintz Road
Wheeling, Illinois 60090

The Contractor/Bidder shall acknowledge in writing on his bid proposal form the receipt of this Addendum.

This Addendum shall be part of the Specifications and Drawings for this project and shall be part of the actual contract document to complete the work. When the Architect issues an Addendum, it is the Bidder's responsibility to copy and insert it into the bid documents they have obtained from the Architect or Owner.

There are Four (4) items in this Addendum.

ITEM NO. 1: PROJECT MANUAL, SECTION 01 10 00 - SUMMARY

1. Add the following to 1.06, Local Codes
 - B. Contact the Village of Glenview, Illinois for information regarding permitting and associated fees. The Roofing Contractor is responsible for obtaining a building permit if required and for any associated fees. <https://www.glenview.il.us/Pages/Building-Permits.aspx>

ITEM NO. 2: DRAWINGS, SHEET A4.1 and A4.2

1. Add Detail Tag 4/A4.3 to ALL Secondary Roof Drains.
2. Replace General Work Note G. with the following:
 - G. Provide removal of the existing roof hatches and installation of four (4) new roof hatches at the existing locations on Roof Areas 1.2, 2.2, 3.0 and 4.0 per Project Manual, Section 07 72 00, 2.02 Roof Hatches. Provide four (4) new Bilco Ladder-Up Safety Posts (LU-1) at roof hatch locations, mounted to the existing roof access ladder per manufacturer installation instructions.
3. Replace the word "and a new 24 ga. prefinished steel cover" in General Work Notes J. with "and new 24 ga. prefinished steel Flush Panels"
 - H. Provide removal of the existing roof hatches and installation of four (4) new roof hatches at the existing locations on Roof Areas 1.2, 2.2, 3.0 and 4.0 per Project Manual, Section 07 72 00, 2.02 Roof Hatches. Provide four (4) new Bilco Ladder-Up Safety Posts (LU-1) at all existing roof hatch locations, mounted to the existing roof access ladder per manufacturer installation instructions.

ADDENDUM NO. 1
ROOF REPLACEMENT AT GLENVIEW TRANSFER STATION
SOLID WASTE AGENCY OF NORTHERN COOK COUNTY (SWANCC)
PROJECT NO. 23122
PAGE 2

ITEM NO. 3: DRAWINGS, SHEET A4.3

1. Regarding Detail 7/A4.3 and 9/A4.3: Replace 16 oz. Copper with 24 ga. Prefinished Steel

ITEM NO. 4: DRAWINGS, SHEET HV1.0

1. This Sheet is "For Reference Only". All work noted on this sheet will be under separate contract.

END OF ADDENDUM NO. 1

BEM
"J:\SWANCC\23122 Roof Replacement @ Glenview Transfer Station\1 Spec\Addendum No. 1\23122AD1.pdf"